

MILITARY SPECIFICATION

MICROCIRCUITS, DIGITAL, 512 BIT, BIPOLAR,
PROGRAMMABLE READ-ONLY MEMORY (PROM), MONOLITHIC SILICON

~~T INACTIVE FOR NEW DESIGN AFTER DATE OF THIS REVISION~~

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the detail requirements for monolithic silicon, PROM microcircuits which employ thin film nichrome resistors as the fusible link or programming element. One product assurance class and a choice of case outlines and lead finishes are provided for each type and are reflected in the part number.

1.2 Part number. The part number shall be in accordance with MIL-M-38510 except the JAN or "J" certification shall not be used.

1.2.1 Device type. The device type shall be as follows:

<u>Device type</u>	<u>Circuit</u>
01	64 words/8 bits per word PROM with open collector
02	64 words/8 bits per word PROM with internal pull-up resistor

1.2.2 Device class. The device class shall be the product assurance level as defined in MIL-M-38510.

1.2.3 Case outline. The case outline shall be designated as follows:

<u>Letter</u>	<u>Case outline (see MIL-M-38510, appendix C)</u>
J	D-3 (24-lead, 1/2" x 1-1/4"), dual-in-line package
K	F-6 (24-lead, 3/8" x 5/8"), flat package
Z	F-8 (24-lead, 1/4" x 3/8"), flat package

1.3 Absolute maximum ratings.

1/ Heat sinking is recommended to reduce junction temperature.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Rome Air Development Center (RBE-2), Griffiss AFB, NY 13441, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Output supply voltage range - - - - -	-0.5 V dc to +7.0 V dc
Output sink current - - - - -	+30 mA
Maximum power dissipation (P_D) ^{2/} - - - -	575 mW dc
Maximum junction temperature (T_J) ^{3/} - - -	175°C

1.4 Recommended operating conditions:

Supply voltage - - - - -	4.75 V dc minimum to 5.25 V dc maximum
Minimum high level input voltage (V_{IH}) - -	2.0 V dc
Maximum low level input voltage (V_{IL}) - -	0.8 V dc
Normalized fanout (each output) ^{4/} - - -	6 maximum (10 mA)
Case operating temperature range (T_C) - - -	-55° to +125°C

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified, the following specification and standard, of the issue listed in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATION

MILITARY

MIL-M-38510 - Microcircuits, General Specification for.

STANDARD

MILITARY

MIL-STD-883 - Test Methods and Procedures for Microelectronics.

(Copies of the specification and standard required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this specification shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Detail specification. The individual item requirements shall be in accordance with MIL-M-38510, and as specified herein. An altered item drawing shall be prepared by the contracting activity to specify the required program configuration.

3.2 Design, construction, and physical dimensions. The design, construction, and physical dimensions shall be as specified in MIL-M-38510 and herein.

3.2.1 Terminal connections. The terminal connections shall be as specified on figure 1.

- 2/ Must withstand the added P_D due to short circuit test (e.g., IOS).
- 3/ Maximum junction temperature shall not be exceeded except for allowable short duration burn-in screening conditions per method 5004 of MIL-STD-883.
- 4/ The device shall fan out in both high and low levels to the specified number of inputs of the same device type as that being tested.

TABLE I. Electrical performance characteristics.

Characteristic	Symbol	Conditions	Device type	Min	Max	Unit
High level output voltage	V _{OH}	V _{CC} = 4.75 V V _{IN} = 0.8 V I _{OH} = 500 μ A	02	2.4	---	V
Low level output voltage	V _{OL}	V _{CC} = 4.75 V V _{IN} = 2.0 V I _{OL} = 10 mA	01 (Ckt A)	---	0.45	V
			01 (Ckt B), 02	---	0.50	V
Input clamp voltage	V _{IC}	V _{CC} = 4.75 V I _{IN} = -12 mA T _C = 25°C	01, 02	---	-1.5	V
Maximum collector cut-off current	I _{CEx1}	V _{CC} = 5.25 V V _{OH} = 2.8 V V _{IN} = 0.8 V	01	---	100	μ A
	I _{CEx2}	V _{CC} = 5.25 V V _{OH} = 5.25 V V _{IN} = 0.8 V	01	---	200	μ A
High level input current	I _{IH1}	V _{CC} = 5.25 V V _{IN} = 2.4 V <u>1/</u>	01, 02	---	60	μ A
	I _{IH2}	V _{CC} = 5.25 V V _{IN} = 5.25 V <u>2/</u>	01, 02	---	100	μ A
Low level input current	I _{IL}	V _{CC} = 5.25 V V _{IN} = 0.4 V <u>2/</u>	01, 02	-0.2	-1.6	mA
Short circuit output current	I _{OS}	V _{CC} = 5.25 V V _{IN} = 0 <u>3/</u>	02	-1.6	-5.0	mA
Supply current	I _{CC}	V _{CC} = 5.25 V V _{IN} = 0	01, 02	---	100	mA
Propagation delay time high-to-low level logic	t _{PHL}	V _{CC} = 5.0 V Figure 6	01, 02	25	140	ns
Propagation delay time low-to-high level logic	t _{PLH}		01, 02	25	140	ns

1/ When testing one E input, apply GND to the other.2/ When testing one E input, apply 5.25 V to the other.3/ Not more than one output shall be grounded at one time.

3.2.2 Truth table.

3.2.2.1 Unprogrammed devices. The truth table for unprogrammed devices for contracts involving no altered item drawing shall be as specified on figure 2. When required in group A, B, or C inspection (see 4.4), the devices shall be programmed by the manufacturer prior to test in a checkerboard pattern (a minimum of 50 percent of the total number of bits programmed) or to any altered item drawing pattern which includes at least 25 percent of the total number of bits programmed.

3.2.2.2 Programmed devices. The truth table for programmed devices shall be as specified by the altered item drawing.

3.2.3 Logic diagrams and schematic circuits. The logic diagrams and schematic circuits shall be as specified on figures 3 and 4.

3.2.4 Case outlines. The case outlines shall be as specified in 1.2.3.

3.3 Lead material and finish. The lead material and finish shall be in accordance with MIL-M-38510 (see 6.5).

3.4 Electrical performance characteristics. The electrical performance characteristics of table I apply over the full recommended case operating temperature range, unless otherwise specified.

3.5 Electrical test requirements. The electrical test requirements for class B devices shall be the subgroups specified in table II. The electrical tests for each subgroup are described in table III.


TABLE II. Electrical test requirements.

MIL-STD-883 test requirements	Subgroups (see table III)
Class B devices	
Interim electrical test parameters (method 5004)	1
Final electrical test parameters (method 5004) for unprogrammed devices	1*, 2, 3, 7*, 8
Final electrical test parameters (method 5004) for programmed devices	1*, 2, 3, 7*, 8, 9
Group A test requirements (method 5005)	1, 2, 3, 7, 8, 9, 10, 11
Group C end-point electrical parameters (method 5005)	1, 2, 3, 7, 8
Group D end-point electrical parameters (method 5005)	1, 2, 3, 7, 8

NOTES:

1. * indicates PDA applies to subgroups 1 and 7 (see 4.2c).
2. Any or all subgroups may be combined when using high speed testers.
3. Subgroups 7 and 8 shall consist of verifying the pattern specified.

Device types 01 and 02 (note 4)



NOTES:

1. G_1 , G_2 and F are connected to ground and H are left open for normal operation.
2. Terminal F is electrically open in device type 01, circuit A and is connected to an internal inverter (9th bit) for device type 01, circuit B and device type 02.
3. Terminal H is electrically open in device type 01, circuit B and device type 02 and is internally connected to the base of the memory transistor for device type 01, circuit A.
4. Pin connections are the same for all case outlines.


FIGURE 1. Terminal connections.

Word No.	INPUTS							OUTPUTS							
	E ¹ /	A ₅	A ₄	A ₃	A ₂	A ₁	A ₀	B ₇	B ₆	B ₅	B ₄	B ₃	B ₂	B ₁	B ₀
X ² /	L	X	X	X	X	X	X	H	H	H	H	H	H	H	H
X	H	X	X	X	X	X	X	L	L	L	L	L	L	L	L

NOTES:

¹/ E = E₁ • E₂²/ X = Irrelevant

FIGURE 2. Truth table (unprogrammed).



NOTES:

1/ Terminal F provides a 9th bit for test purposes only.

2/ AR₁ = 3kΩ and AR₂ = AR₃ = AR₄ = 2.2kΩ except in amplifier-inverter A₅ where AR₁ = 2.2kΩ, AR₂ = AR₄ = 1.2kΩ and AR₃ = 1.8kΩ.

3/ The 2kΩ pull-up resistor is used for device type 02 only.

4/ All resistance values are nominal.

5/ G₂ and G'₂ are internally connected together.

FIGURE 3. Logic diagram and schematic circuit for device type 01,
circuit B and device type 02.





FIGURE 3. Logic diagram and schematic circuit for device type 01,
circuit B and device type 02 - Continued.





FIGURE 3. Logic diagram and schematic circuit for device type 01,
circuit B and device type 02 - Continued.




FIGURE 3. Logic diagram and schematic circuit for device type 01,
circuit B and device type 02 - Continued.




FIGURE 4. Logic diagram and schematic circuit for device type 01, circuit A.







FIGURE 4. Logic diagram and schematic circuit for device type 01, circuit A - Continued.



NOTE: All resistance values are nominal.

FIGURE 4. Logic diagram and schematic circuit for device type 01, circuit A - Continued.



NOTE: $R = 470\Omega \pm 5\%$. All bit outputs shall have separate identical loads.

FIGURE 5. Burn-in and steady state life test circuit for device types 01 and 02.







FIGURE 5. Burn-in and steady state life test circuit for device types 01 and 02 - Continued.



NOTES:

1. Pins 12 and 14 shall be left open.
2. Terminal conditions shall be as specified on table III.
3. $C_1 = .05 \mu\text{F} \pm 10\% \text{ percent}$; $R_1 = 51\Omega \pm 5\% \text{ percent}$; $R_2 = 470\Omega \pm 5\% \text{ percent}$; $R_3 = 1 \text{ k}\Omega \pm 5\% \text{ percent}$, $C_L = 30 \text{ pF minimum including jig and probe capacitance}$.


FIGURE 6. Switching time test circuit.



NOTES:

- 1/ Connect -5.0V to G₁ before applying V_{cc} or programming voltage.
- 2/ For device type 01, circuit A, G'₂ shall be open,
- 3/ For device types 01, circuit B, and 02, G'₂ shall be 0V.
- 3/ Generator characteristics are defined in 4.6.

FIGURE 7a. Programming circuit.



NOTES:

1. Q₁ = 2N2907 or equivalent.
2. Q₂ = 2N1613 or equivalent.
3. CR1 = 1N4573 or equivalent.

FIGURE 7b. Alternate high speed programming circuit.

TABLE III. Group A Inspection for device type Q1.
Terminal conditions: Outputs not designated are open or coupled to GND or
voltage; inputs not designated are high 0.8 V. Low 0.8 V, or open.

Subgroup	Symbol	MIL-STD-883C Test Method	Test Results												Measured terminal Min Max				Test limits							
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
	I_{IC}		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
	V_{IC}		3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26
	V_{IC} at $T_c = 25^\circ C$		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
I_{IL}	V_{IL}	3009	0	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V												
I_{IL}	V_{IL}	3010	17	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V												
I_{IL}	V_{IL}	3011	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42
I_{IL}	V_{IL}	3012	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48
I_{CE1}	V_{CE1}	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57
I_{CE2}	V_{CE2}	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65
I_{CC}	V_{CC}	3005	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72
V_{OL}	V_{OL}	3007	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73

See footnotes at end of device type 01.

TABLE III. GROUP A INSPECTION FOR DEVICE TYPE OI - Continued.
 Terminal conditions: Outputs not designated are open or resistive coupled to GND or
 voltage; inputs not designated are high ≥ 2.0 V, low ≤ 0.8 V, or open.

Subgroup	Symbol	MIL-STD-883C method no.	Testes	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	Measured terminal voltage Max	Test limits unit
2 1/	Same tests, terminal conditions, and limits as for subgroup 1, except $T_c = 125^\circ\text{C}$ and Vic tests are omitted.																												
3 1/	Same tests, terminal conditions, and limits as for subgroup 1, except $T_c = -55^\circ\text{C}$ and Vic tests are omitted.																												
7 2/4/ $T_c = 25^\circ\text{C}$	Truth table tests		58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121																										

See footnotes at end of device type OI.

TABLE III. Group A Inspection for device type 01 - Continued.

Subgroup	Symbol	MIL-STD-883 Method	Test	Notes	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	Measured	Test limits	
			No.	NC	A ₀	A ₁	A ₂	A ₃	A ₄	A ₅	A ₆	A ₇	A ₈	A ₉	A ₁₀	A ₁₁	A ₁₂	A ₁₃	A ₁₄	A ₁₅	A ₁₆	A ₁₇	A ₁₈	A ₁₉	A ₂₀	A ₂₁	A ₂₂	A ₂₃	A ₂₄	Min	Max
9 T _C = 25°C and -55°C	T _{PH} and T _{PLH}	3001 (Fig. 6)	250																												
		251																													
		253																													
		254																													
		255																													
		257																													
		258																													
		260																													
		261																													
		262																													
		263																													
		264																													
		265																													
10																															
11																															

1/ Unprogrammed device conditions.

2/ V_{OL} = 0.45 V for circuit A and 0.50 V for circuit B.

3/ Input voltages shall be: A = 2.0 V minimum; B = 0.8 V maximum.

4/ Output voltages shall be either:

- a. H = 2.1 V minimum and L = V_{OL} (V_{OL} = 0.45 V maximum for circuit A and 0.50 V maximum for circuit B) when using a high speed switcher about 10° C temperature.
- b. H 2.0 V and L < 1.0 V when using a high speed cheater single comparator.

- 5/ Terminal conditions (GND or 5.0 V) shall be as specified on figure 6 or in the altered item drawing, as applicable, so that all outputs are at a low logic level.

TABLE III. Group A inspection for device type 02.
Terminal conditions: Outputs not designated are open or resistive coupled to GND or
voltage; inputs not designated are high 2.0 V, low 0.8 V, or open.

Subgroup	Symbol	MIL-STD-883 test method No.	Measured limits												Test limit										
			1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
1.1L	V _{TC}	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		2	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		3	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		4	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		5	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		6	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		7	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		8	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
1.1L	3009	9	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V	0.4 V
		10	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		11	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		12	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		13	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		14	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		15	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		16	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
1.1H	3010	7	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V	2.4 V
		15	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		20	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		21	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		22	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		23	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		24	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
1.1H	3012	5	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V	5.25 V
		16	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		26	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		27	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		28	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		29	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		30	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		31	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		32	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
1.CC	3005	33	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND
		34	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		35	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		36	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		37	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		38	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		39	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		40	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		41	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Vol	3007	42	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V	2.0 V
		43	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		44	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		45	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		46	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		47	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		48	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		49	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		50	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
10S	3011	51	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND	GND
		52	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		53	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		54	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		55	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		56	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
		57	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

See footnotes at end of device type 02.

TABLE III. Group A Inspection for device type 02. Continued.
Terminal conditions: Output terminals ~~connected to GND or V_{DD}~~ connected to GND or V_{DD} or open; Input terminals are High ($\geq 2.0 \text{ V}$, low ($\leq 0.8 \text{ V}$), or open.

Subgroup	Symbol	MIL-SID-885- method no.	Terminals	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	Measured terminal Min Max	Test limits Unit
2 1/																													
3 1/																													
7 2/3/ $T_c = 25^\circ\text{C}$	Touch table test	58																											
		59																											
		60																											
		61																											
		62																											
		63																											
		64																											
		65																											
		66																											
		67																											
		70																											
		71																											
		72																											
		73																											
		74																											
		75																											
		76																											
		77																											
		79																											
		80																											
		81																											
		82																											
		83																											
		84																											
		85																											
		86																											
		87																											
		88																											
		89																											
		90																											
		91																											
		92																											
		93																											
		94																											
		95																											
		96																											
		97																											
		98																											
		99																											
		100																											
		101																											
		102																											
		103																											
		104																											
		105																											
		106																											
		107																											
		108																											
		109																											
		110																											
		111																											
		112																											
		113																											
		114																											
		115																											
		116																											
		117																											
		118																											
		119																											
		120																											
		121																											

See footnotes at end of device type 02.

TABLE III. Group A Inspection for device type 02 - Continued.
Terminal conditions: Outputs not designated are open or resistive coupled to GND or
voltage; Inputs not designated are high 2.0 V, low -0.8 V, or open.

Subgroup	Symbol	MIL-STD-883- method	Cases J,K,L test no.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	Measured limits terminal	Test limits terminal
T _C = 125°C and -55°C test	Truth table		122-	Repeat subgroup 7, except T _C = 125°C.																									
			185-	Repeat subgroup 7, except T _C = -55°C.																									
T _C = 25°C	t _{PHL} and t _{PLH}	(Fig. 6)	249																										
			351																										
			252																										
			254																										
			255																										
			256																										
			257																										
			258																										
			259																										
			260																										
			261																										
			262																										
			263																										
			264																										
			265																										
			-																										
10				Same tests and terminal conditions as for subgroup 9, except T _C = 125°C and the limits are 25 ns minimum and 140 ns maximum.																									
11				Same tests, terminal conditions, and limits as for subgroup 10, except T _C = -55°C.																									

1/ Unprogrammed device conditions.

2/ Input voltages shall be: A = 2.0 V minimum; B = 0.8 V maximum.

3/ Output voltages shall be either:

a. H = 2.4 V minimum and L = 0.5 V maximum when using a high speed cheater double comparator.

b. H = 2.0 V and L < 1.0 V when using a High speed cheater single comparator.

4/ Terminal conditions (GND or 5.0 V) shall be as specified on figure 6 or in the altered item drawing, as applicable, so that all outputs are at a low logic level.

3.6 Marking. Marking shall be in accordance with MIL-M-38510. For programmed devices, the altered item drawing number shall be added to the marking by the programming activity. The JAN or "J" certification shall not be used.

3.7 Processing options. Since the PROM is an unprogrammed memory capable of being programmed by either the manufacturer or the user to result in a wide variety of ROM configurations, two processing options are provided for selection in the contract, using an altered item drawing.

3.7.1 Unprogrammed PROM delivered to the user. All testing shall be verified through group A testing as defined in 3.2.2.1 and tables II and III. It is recommended that users perform subgroups 7 and 9 after programming to verify the specific program configuration.

3.7.2 Manufacturer-programmed PROM delivered to the user. All testing requirements and quality assurance provisions herein, including the requirements of the altered item drawing, shall be satisfied by the manufacturer prior to delivery.

3.8 Microcircuit group assignment. The devices covered by this specification shall be in microcircuit group number 14 (see MIL-M-38510, appendix E).

3.9 Manufacturer eligibility. To be eligible to supply microcircuits to this specification a manufacturer shall have a manufacturer certification in accordance with MIL-M-38510 for at least one line, not necessarily the line producing the device type described herein.

3.10 Certification. Certification in accordance with MIL-M-38510 is not required for this device.

4. QUALITY ASSURANCE PROVISIONS

4.1 Sampling and inspection. Sampling and inspection procedures shall be in accordance with MIL-M-38510 and methods 5005 and 5007, as applicable, of MIL-STD-883, except as modified herein.

4.2 Screening. Screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection. The following additional criteria shall apply:

- a. Burn-in test (method 1015 of MIL-STD-883); test condition D or E, using the circuit shown on figure 5 or equivalent.
- b. Interim and final electrical test parameters shall be as specified in table II, except interim electrical test parameters prior to burn-in is optional at the discretion of the manufacturer.
- c. The percent defective allowable (PDA) shall be as specified in MIL-M-38510.
- d. Class B devices processed to an altered item drawing may be programmed either before or after burn-in at the manufacturer's discretion. The required electrical testing shall include, as a minimum, the final electrical tests for programmed devices as specified in table II herein.

4.3 Qualification inspection. Qualification inspection is not required.

4.4 Quality conformance inspection. Quality conformance inspection shall be in accordance with MIL-M-38510. Inspections to be performed shall be those specified in method 5005 of MIL-STD-883 and herein for groups A, B, C, and D inspections (see 4.4.1 through 4.4.4). Generic test data may be used to satisfy the requirements for group C and D inspections (see 6.7).

4.4.1 Group A inspection. Group A inspection shall be in accordance with table I of method 5005 of MIL-STD-883 and as follows:

- a. Tests shall be as specified in table II herein.
- b. Subgroups 4, 5, and 6 shall be omitted.

- c. Devices selected for testing in subgroups 9, 10, and 11 shall be programmed in accordance with 3.2.2.
- d. A programmability test shall be performed when programming the sample (12 devices) used in subgroups 9, 10, and 11 (see 3.2.2.1). If more than two devices fail to program, the lot shall be rejected. If an additional sample is used (24 total devices), the lot shall be rejected if more than 4 devices fail to program.

4.4.2 Group B inspection. Group B inspection shall be in accordance with table II of method 5005 of MIL-STD-883.

4.4.3 Group C inspection. Group C inspection shall be in accordance with table III of method 5005 of MIL-STD-883 and as follows:

- a. End-point electrical parameters shall be as specified in table II herein.
- b. Steady state life test (method 1005 of MIL-STD-883) conditions:
 - (1) Test condition D or E, using the circuit shown on figure 5 or equivalent.
 - (2) $T_A = 125^\circ\text{C}$ minimum.
 - (3) Test duration - 1,000 hours, except as permitted by appendix B of MIL-M-38510 and method 1005 of MIL-STD-883.
- c. For quality conformance inspection, the programmability sample (see 4.4.1d) shall be included in the subgroup 1 tests.

4.4.4 Group D inspection. Group D inspection shall be in accordance with table IV of method 5005 of MIL-STD-883. End-point electrical parameters shall be as specified in table II herein.

4.5 Methods of inspection. Methods of inspection shall be as specified in the appropriate tables and as follows:

4.5.1 Voltage and current. All voltages given are referenced to the microcircuit ground terminal. Currents given are conventional and positive when flowing into the referenced terminal.

4.6 Programming. Using the test conditions of table IV, the following procedure shall be used for programming the device:

- a. Connect the device as shown on figure 7a, using the fusing generator of figure 7a or the alternate circuit of figure 7b. The circuit shown on figure 7b can be used in more automated programming systems. This circuit generates a current pulse which is at the proper voltage and current levels for fast reliable programming. The input programming pulse width shall be 750 ± 50 milliseconds. The number of attempts to program a given bit shall be as specified in table IV.
- b. To address a particular word in the memory, set the input switches to the binary equivalent of that word, where a logical low level is -5.0 V and a logical high level is an open circuit. (Do not return to supply.) All output bits (B_0, B_1, \dots, B_7) of this word are not available for programming.
- c. With the output current limited (as specified in table IV), apply a negative going current pulse to the pin associated with the first bit to be changed from a logical low level to a logical high level. This is most easily accomplished by connecting the negative terminal of a variable power supply output pin and manually increasing the voltage to approximately 6.0 volts.
- d. Skipping any bit which is to remain a logical low level, repeat 4.6c for each logical low level in the word being addressed. Not more than one bit shall be programmed at a time.

- e. Set the next input address and repeat 4.6c and d. This procedure is repeated for each input address for which a specific output word pattern is desired. Note that all addresses do not have to be programmed at the same time, nor do all output bits for a given address. A logical low level can always be changed to a logical high level, simply by repeating 4.6b and c. A logical low level, once programmed to a logical high level, cannot be reprogrammed.

TABLE IV. Programming specifications.

Parameter		Value
Address input voltage	High logic level	Open circuit ^{1/}
	Low logic level	-5.0 V
Power supply voltage		+5.0 V +5%, -0%
G ₁ voltage ^{2/}		-5.0 V
G ₂ voltage		0 V
G' ₂ voltage	Device type 01 (circuit A)	Open
	Device types 01 (circuit B) and 02	0 V
Maximum programming voltage		-7.0 V
Maximum programming current		100 mA
Maximum number of attempts to program a given bit		2
Maximum case temperature during programming		75°C

^{1/} Open collector TTL gates meet this requirement.

^{2/} G₁ must be connected to -5.0 V prior to applying V_{CC} or programming voltage.

5. PACKAGING

5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-M-38510.

6. NOTES

6.1 Intended use. Microcircuits conforming to this specification are intended for original equipment design applications and logistic support of existing equipment.

6.2 Ordering data. The acquisition document should specify the following:

- a. Complete part number (see 1.2).
- b. Requirements for delivery of one copy of the quality conformance inspection data pertinent to the device inspection lot to be supplied with each shipment by the device manufacturer, if applicable.
- c. Requirements for certificate of compliance, if applicable.

- d. Requirements for notification of change of product or process to the contracting activity in addition to notification to the qualifying activity, if applicable.
- e. Requirements for failure analysis (including required test condition of method 5003 of MIL-STD-883), corrective action, and reporting of results, if applicable.
- f. Requirements for product assurance options.
- g. Requirements for special carriers, lead lengths, or lead forming, if applicable. These requirements shall not affect the part number. Unless otherwise specified, these requirements will not apply to direct purchase by or direct shipment to the Government.
- h. Requirements for programming the device, including processing option.

6.4 Abbreviations, symbols, and definitions. The abbreviations, symbols, and definitions used herein are defined in MIL-M-38510, MIL-STD-1331, and as follows:

GND - - - - -	Electrical ground (common terminal).
VIN - - - - -	Voltage level at an input terminal.
VIC - - - - -	Input clamp voltage.
IIN - - - - -	Current flowing into an input terminal.

6.5 Logistic support. Lead materials and finishes (see 3.3) are interchangeable. Unless otherwise specified, microcircuits acquired for Government logistic support will be acquired to device class B (see 1.2.2) and lead material and finish C (see 3.3). Longer lead lengths and lead forming shall not affect the part number. It is intended that spare devices for logistic support be acquired in the unprogrammed condition (see 3.7.1) and programmed by the maintenance activity, except where use quantities for devices with a specific program or pattern justify stocking of preprogrammed devices.

6.6 Substitutability. The cross-reference information below is presented for the convenience of users. Microcircuits covered by this specification will functionally replace the listed generic-industry type. Generic-industry microcircuit types may not have equivalent operational performance characteristics across military temperature ranges or reliability factors equivalent to MIL-M-38510 device types and may have slight physical variations in relation to case size. The presence of this information shall not be deemed as permitting substitution of generic-industry types for MIL-M-38510 types or as a waiver of any of the provisions of MIL-M-38510.

<u>Military device type</u>	<u>Generic-industry type</u>
01	HROM- 0512, MCM 5303
02	MCM 5304

6.7 Generic test data. Generic test data may be used to satisfy the requirements of 4.4.3. Group C generic test data shall be on date codes no more than one year old and on a die in the same microcircuit group (see appendix E of MIL-M-38510) with the same material, design and process from the same plant as the die represented. Group D (see 4.4.4) generic data shall be on date codes no more than one year old and on the same package type (see terms, definitions, and symbols of MIL-M-38510) and from the same plant as the package represented. The vendor is required to retain generic data for a period of not less than 36 months from the date of shipment.

6.8 Ordering guidance. Since the qualification and certification requirements have been removed from the specification, orders may be placed immediately.

6.9 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodians:

Army - ER
Navy - EC
Air Force - 17

Review activities:

Army - AR, MI
Navy - OS, SH
Air Force - 11, 19, 85, 99
DLA - ES

User activities:

Army - SM
Navy - AS, MC,

Preparing activity:

Air Force - 17

Agent:

DLA - ES

(Project 5962-0880)